

DEMOLITION REQUIREMENTS

Rev 1/09

All structures shall be completely razed. All floor construction over basements shall be removed: interior basements partitions and pieces of solid masonry construction shall be completely removed. All basements, cellar or foundation walls shall be completely removed. Masonry floors may be cracked and used as backfill if more than 18 inches below ground level.

It is the responsibility of the permit holder to cap the Sewer line under direct supervision of the Waynesburg Street Department Supervisor.

All material from the structure must be removed and taken to an approved landfill. Transport of said materials must be in an approved container or by an approved hauler with a Municipal Waste Hauling License. With proof of same supplied to the Borough Manger as a copy of receipt from the landfill.

Backfilling of all subsurface areas shall conform to the requirements of PADOT Form 408/Specification Section 206.2 and Section 206.3 and the following provisions: No backfilling before inspection by the Waynesburg Street Department Supervisor. All filled is to be hauled in and not gouged from the surrounding terrain. Existing cellar floors and other surface areas shall be broken to insure adequate drainage. The final 18 inches to the existing ground level shall be filled with clean dirt and leveled to grade. Final grading shall include 2 inches of topsoil with seeding of grass.